

Govt. of India
Archaeological Survey of India,
Jagdalpur Sub- Circle , Jagdalpur

No.- JDP/S.R./Bhairamgarh -17-18- (40)

DATE :-15/03/2018

QUOTATION CALL NOTICE

Sealed quotations are hereby invited from the eligible contractors having valid registration for the execution of following items for the work of **VEGETATION CLEARANCE, DISTEMPERING, PAINTING, LAYING SANDSTONE FLOORING, AND REPAIRING BOUNDARY WALL Under MW (Con) for SRs to Bhairamdev Temple, Bhairamgarh for 17/18 UPTO 21/03/2018.**

The quotation must be addressed to The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, Raipur.

The quotation will be opened on **22/03/2018** at 3.00 P.M.in the O/O The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, Raipur.


The competent authority reserved the right to accept or reject any or all quotation without assigning any reason thereof.

Item No.	Item of work	Quantity	Remarks
1.	Provision for removal of vegetational growth from the all area of the monument except garden area including disposal of refused lead upto 50m approximate	50.00 Unit	
2.	Provision for Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand	175.25 m2	
3 (C)	Providing and laying of 75 mm thick rubbed sand stone with over 20 mm average thick base of lime mortar in ratio 1:1:1 (one un-slaked lime, one surkhi 1st class, one course sand) to match the said of stone and pointing with same mortar including supply of materials, labours and T&P etc. (on already laid concrete)	28.52 m2	Rates should be quoted including contractor profit and all taxes like GST (12%) etc.
4	Provision for repair of damaged boundary wall and grill fixing		
4 (A)	Provision for repair of boundary wall with random rubble stone masonry with lime mortar in ratio 1:1:1 (one lime-unslaked, one surkhi 1st class, one course sand) including supply of all materials, labours and T&P etc.	9.42 m3	
4 (B)	Provision for fixing of grill over boundary wall excluding concrete etc all complete including supply of all materials, labours and T&P etc.	23.00 m2	
4 (C)	Provision for providing and laying of lime concrete with lime mortar in ratio 1:1:1:4 (one unslaked lime, one surkhi 1st class, one coarse sand and four brick aggregate in 20mm nominal size) including slacking of lime, mixing ingredient and beating compaction etc. all completed. (for coping and block for grill fixing)	0.57 m3	
5	Provision for Distempering to the inner wall of the shed with oil bound washable distemper of approved brand and manufacture to give an even shade Old work (one or more coats)	85.92 m2	

1
Sr. C.A., A.S.I., BS

Copy to – 1. The Notice Board .

2- The S.A., A.S.I., Raipur with the request to make effort for its wide publicity.


15/3/18
Sr. C.A., A.S.I., BSP