

REQUEST FOR PROPOSAL

COMPREHENSIVE ESTIMATE OF THE CENTRALLY PROTECTED MONUMENT LAXMAN TEMPLE AT
SIRPUR UNDER RAIPUR SUB-CIRCLE, RAIPUR (C.G.)

REFERENCE NO. F. No. 15-1/387/19-20-W

Dated 06.06.2019



सत्यमेव जयते

GOVERNMENT OF INDIA
MINISTRY OF CULTURE
ARCHAEOLOGICAL SURVEY OF INDIA
RAIPUR CIRCLE
RAIPUR



Section-1

Table — A: Time and Work Frame

NAME OF WORK: COMPREHENSIVE ESTIMATE OF THE CENTRALLY PROTECTED MONUMENT LAXMAN TEMPLE AT SIRPUR UNDER RAIPUR SUB-CIRCLE, RAIPUR (C.G.)

Tender Reference No. 15-1/387/19-20-W Dated 06.06.2019

Manual bids shall not be accepted.

CRITICAL DATE SHEET

1.	Publishing Date	15.07.2019	3.00 PM.
2.	Document Download / Sale Start Date	15.07.2019	3.30PM.
3.	Seek Clarification Start Date	16.07.2019	3.00 PM.
4.	Seek Clarification End Date	06.08.2019	3.00PM
5.	Pre Bid Meeting Date	06.08.2019	11.00AM
6.	Bid Submission Start Date	15.07.2019	3.30PM
7.	Bid Submission Closing Date	06.08.2019	3.00PM
8.	Bid (technical) Opening Date	07.08.2019	3.30PM
9.	Validity of bid		



Sir,

1. The Archaeological Survey of India invites Online Bids in the prescribed form under the Two Bid system (a) Technical Bid and (b) Financial Bid for execution of work with materials for the work of COMPREHENSIVE ESTIMATE OF THE CENTRALLY PROTECTED MONUMENT LAXMAN TEMPLE AT SIRPUR UNDER RAIPUR SUB-CIRCLE, RAIPUR (C.G.)
2. The system of e-tendering shall be adopted, comprising Technical Bid and the Financial Bid. **Document Download: Tender documents may be downloaded from CPPP site <https://eprocuregov.in/eprocure/app> as per the schedule given in CRITICAL DATE SHEET.**
Technical Bid should, inter alia, contain all technical details of services and solutions to be provided along with such documentary proofs. Financial Bid should, inter alia, indicate item-wise price and other commercial / financial terms against the items mentioned in the Technical Bid.
3. **Bid Submission:**
Applicants/ intending or interested Bidders are invited to submit their online proposal after carefully reading the tender document by providing (a) Technical Bid, and (b) Financial Bid, separately, clearly mentioning (i) 'Technical Cover', and (ii) 'Financial Cover' respectively. Such proposals are to be submitted online within the stipulated date and time as mentioned in the Bid document as given in **CRITICAL DATE SHEET.**
Bids shall be submitted online only at CPPP website: <https://eprocure.gov.in/eprocure/app>
Bid documents may be scanned with 100 dpi with black and white option which help in reducing size of the scanned document.
4. **Earnest Money Deposit:**
The Hard Copy of original instruments in respect of earnest money must be delivered to the Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan", 1st floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur-492006 on or before Bid opening date/ time as mentioned in critical date sheet. Tender shall be liable for legal action for non-submission of original payment instrument like FDR against the submitted Bid. The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization National Small Industries Corporation(NSIC) or as per applicable. The earnest money should be in the form of FDR drawn in favour of the "SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA" payable at Raipur of any nationalized bank.
5. **Tender Fee: Rs. 5000/ (non-refundable)-** (Rs. Five thousand Only) in shape of Demand Draft in favour of "SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA" payable at Raipur of any nationalized bank.
6. **Estimated Cost of Tender: Rs. 10305387/-** (Rs. One crore three lacs five thousand three hundred and eighty seven only)

Address for communication is as given below:

Contact Details:

Contact Person	Superintending Archaeologist
Address for communication	O/o The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan", 1 st floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur-492006



File No. 15-1/387/19-20-W-
Government of India
Archaeological Survey of India
O/o Superintending Archaeologist, Raipur Circle,
Poorvayatan", 1st floor,
Govind Sarang Commercial Complex,
Raipur, Chhattisgarh-492006
Phone No./Fax : 0771-4218483/84
E-mail : circleraipur.asi@gov.in , circleraipur.asi@gmail.com



Name of work: COMPREHENSIVE ESTIMATE OF THE CENTRALLY PROTECTED MONUMENT
LAXMAN TEMPLE AT SIRPUR UNDER RAIPUR SUB-CIRCLE, RAIPUR (C.G.)

Estimated Cost: Rs. 10305387/- (Rs. One crore three lacs five thousand three hundred and eighty seven only)

READ TERMS AND CONDITION BEFORE FILLING UP THE SCHEDULE AND SIGN ON ALL PAGES.

S. No.	Name of item	Quantity	Per Unit
1.	Provision for racking out the old damaged/sunken pointing from the front wall (northern side & Southern side of the temple) etc.	34.16	Sqm
2.	Provision for providing recess pointing with use of traditional mortar of racked joints to 1:1:1 etc	34.16	Sqm
3(a)	Provision for taking out the old flooring from the parikrama platform of the Laxman temple.	9.70	Cum
3(b)	Providing and laying lime concrete (1:1:1:4) base for stone flooring.	9.70	Cum
3(c)	Providing and laying 40 to 50mm thick cist stone plate using 60% new matching to the structure etc including chiseling of the stone properly and recess pointing in 1:1:1 Lime sand mortar etc.	194.05	Sqm
4	Provision for providing and fixing of wooden railing all around platform and ramp by use sal wood for Divyang tourists and other one in the front side of the Laxman Temple, Sirpur	12.39	cum
6	Provision for petty materials Fastners, serve clamp and items etc complete.		
	a. Fevicol	30.00	Kg
	b. Nails different size	20.00	Kg
	c. Nut bolt/clamp	20.00	Kg
	d. Aerolite and hardner(this material will be used for new railing and also for old damaged existing railing etc.)	33.00	Kg
10	Provision for taking out damaged sun-mica from the existing pedestal in SS-1 & SS-2 etc with making surface dust free including fixing of new laminated sun-mica sheet with use of bounding material in proper manner etc	161.00	Sqm
11	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc using process as describe in DSR	520.68	Sqm
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	1160.74	Sqm
13	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied etc	826	Rmt
14	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	3093.75	Kg
15	Racking out the damaged pointing from boundary wall.	3130.40	Sqm
16	Provision for providing recess pointing with use of traditional mortar of racked joints	3130.40	Sqm

17	Provision for providing and installation of 250litre RO water plant etc. including supply of all materials, labour and T&P etc. (Specification attached).	1	job
18	Provision for checking of operation & repairing of lighting conductor (1 Nos for Repairing and 2 Nos new for Sculpture Shed).		
A.	Providing and fixing copper lightning rod with multiple spikes (5/8" dia and 1 meter long) at the top of the monument with dumble insulator on the metal fixture etc. complete.	2.00	Nos.
B.	Supply and laying of copper strip (25 X 5 mm thick) fitted from the bottom of lightning rod to earth pit with the help of clips (manufactured from copper alloy) through the exterior wall surface of the monument with due bending the strip as per requirement with proper care and as per the instruction of the Engineer's of this circle office.	8.00	RMT
C.	Provision for earth pit (1 m dia and 2.5 m depth) with providing 40 mm dia perforated GI tube with C.I point at bottom with due fitting the copper strips in prper way and filling the pit alternate layer of charcoal and coarse salt and finally soil filling and complete in all respect with "Megger" testing report.	2.00	Nos.
D	For repair work		
	Provision for checking and repairing of lighting conductor with installation and fixing of necessary requirement including revival of earth pit by way of supplying and filling charcoal and salt etc.	1	Job
19	Provision of providing and fixing of net/jail made of angle iron frame structure painting with matching with the monuments including SS Jali also painted with matching to the monument at Sukhnashika of the Laxman temple etc(proper care should be taken during fixing of the same and it should be ensured that the structure should not be damaged.)	1	job
20	Provision for providing of sitting benches etc(providing and fixing of red sand stone benches having 4 legs of size 0.26 x 0.26 x 0.45 m with simple molding and 8cm thick red sand stone top size 1.50 x 0.60m as per design and matching to the existing pattern at the site etc.	20	Each
21	Provision for purchase and installation at site of readymade dustbins of Red sand stone of cyndrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape and design.	10	Each
22	Provision for providing and fixing of information signage board of 50mm thick red sand stone slab of size 1050 x 750mm with engraved/etched and color filled as per approved text and art work placed over brick masonry pier of size 350 x 350 x 1200mm claded on all size with 25mm thick red sand stone slabs including PCC base in 1:2:4 of size 600 x 600 x 100mm including excavation of pit to be 250mm dip and lying complete as per design and existing pattern.		
A.	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan),including dressing of side sand ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	0.18	Cum
B.	Provision for providing and laying mechanical mix plain cement concrete 1:3:6 (1 Cement : 3 Coarse Sand : 6 Stone Aggregate 40mm nominal size) with crushed stone aggregate excluding cost of centering and shuttering with 40mm nominal size grade aggregates m -7.5 in foundation .	0.07	Cum
C.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in all shapes and sizes in Cement mortar 1:4 (1 cement :4 coarse sand)	0.23	Cum



