

**REQUEST FOR PROPOSAL**

COMPREHENSIVE ESTIMATE FOR CONSERVATION AND DEVELOPMENT OF THE AREA SURROUNDING  
OF DANTESHWARI DEVI TEMPLE AT DANTEWADA

REFERENCE NO. F. No. T-15/24/Dec/19/2182519/NAP Dated 03.12.2019



सत्यमेव जयते

GOVERNMENT OF INDIA  
MINISTRY OF CULTURE  
ARCHAEOLOGICAL SURVEY OF INDIA  
RAIPUR CIRCLE  
RAIPUR



*[Handwritten signature]*  
31/12/19

Section-1

Table — A: Time and Work Frame

**NAME OF WORK:** COMPREHENSIVE ESTIMATE FOR CONSERVATION AND DEVELOPMENT OF THE AREA SURROUNDING OF DANTESHWARI DEVI TEMPLE AT DANTEWADA

**Tender Reference No.** T-15/24/Dec/19/2182519/NAP **Dated:-03.12.2019**

**Manual bids shall not be accepted.**

CRITICAL DATE SHEET

1.	Publishing Date	01.01.2020	03:00 P.M.
2.	Document Download / Sale Start Date	01.01.2020	03:30 P.M.
3.	Seek Clarification Start Date	01.01.2020	04:30 P.M.
4.	Seek Clarification End Date	22.01.2020	03:00 P.M.
5.	Pre Bid Meeting Date	22.01.2020	11:00 A.M.
6.	Bid Submission Start Date	01.01.2020	03:30 P.M.
7.	Bid Submission Closing Date	22.01.2020	03:00 P.M.
8.	Bid (technical) Opening Date	23.01.2020	03:30 P.M.
9.	Validity of bid	60 days	



*[Handwritten signature]*  
31/12/19

Sir,

1. The Archaeological Survey of India invites Online Bids in the prescribed form under the Two Bid system (a) Technical Bid and (b) Financial Bid for execution of work with materials for the work of COMPREHENSIVE ESTIMATE FOR CONSERVATION AND DEVELOPMENT OF THE AREA SURROUNDING OF DANTESHWARI DEVI TEMPLE AT DANTEWADA
2. The system of e-tendering shall be adopted, comprising Technical Bid and the Financial Bid. **Document Download: Tender documents may be downloaded from CPPP site <https://eprocuregov.in/eprocure/app> as per the schedule given in CRITICAL DATE SHEET.**  
Technical Bid should, inter alia, contain all technical details of services and solutions to be provided along with such documentary proofs. Financial Bid should, inter alia, indicate item-wise price and other commercial / financial terms against the items mentioned in the Technical Bid.
3. **Bid Submission:**  
Applicants/ intending or interested Bidders are invited to submit their online proposal after carefully reading the tender document by providing (a) Technical Bid, and (b) Financial Bid, separately, clearly mentioning (i) 'Technical Cover', and (ii) 'Financial Cover' respectively. Such proposals are to be submitted online within the stipulated date and time as mentioned in the Bid document as given in **CRITICAL DATE SHEET.**  
Bids shall be submitted online only at CPPP website: <https://eprocure.gov.in/eprocure/app>  
Bid documents may be scanned with 100 dpi with black and white option which help in reducing size of the scanned document.
4. **Earnest Money Deposit:**  
The Hard Copy of original instruments in respect of earnest money must be delivered to the Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan", 1<sup>st</sup> floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur-492006 on or before Bid opening date/ time as mentioned in critical data sheet. Tender shall be liable for legal action for non-submission of original payment instrument like FDR against the submitted Bid. The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization National Small Industries Corporation (NSIC) or as per applicable. The earnest money should be in the form of FDR drawn in favour of the "SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA" payable at Raipur of any nationalized bank.
5. **Tender Fee: Rs. 500/ (non-refundable)-** (Rs. Five Hundred Only) in shape of Demand Draft in favour of "SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA" payable at Raipur of any nationalized bank.
6. **Estimated Cost of Tender: Rs. 4998691/-** (Rupees forty nine lacs ninety eight thousand six hundred and ninety one only)
7. **Earnest Money: Rs. 124967.00** (Rupees one lac twenty four thousand nine hundred and sixty seven only)

Address for communication is as given below:

**Contact Details:**

<b>Contact Person</b>	Superintending Archaeologist
<b>Address for communication</b>	O/o The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan", 1 <sup>st</sup> floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur-492006



*[Handwritten signature]*  
31/12/19

No. T-15/24/Dec/19/2182519/NAP  
 Government of India  
 Archaeological Survey of India  
 O/o Superintending Archaeologist, Raipur Circle,  
 Poorvayatan", 1<sup>st</sup> floor,  
 Govind Sarang Commercial Complex  
 Raipur, Chhattisgarh-492006  
 Phone No./Fax : 0771-4218483/84,  
 E-mail : circleraipur.asi@gov.in , circleraipur.asi@gmail.com

**Name of work:** COMPREHENSIVE ESTIMATE FOR CONSERVATION AND DEVELOPMENT OF THE AREA SURROUNDING OF DANTESHWARI DEVI TEMPLE AT DANTEWADA

**Estimated Cost:** Rs. 4998691/- (Rupees forty nine lacs ninety eight thousand six hundred and ninety one only)

READ TERMS AND CONDITION BEFORE FILLING UP THE SCHEDULE AND SIGN ON ALL PAGES

S. No.	Name of item	Quantity	Per Unit
1	Provision for supply and fixing of sal wood (different sizes) for replacement of old damaged wood of rafter, Struts, purlins and supporting pillar including Transportation, Labour and T&P etc Complete	1.62	M3
2	Provision for painting two or more coat with synthetic enamel paint to the new wooden work of temple including under coat of suitable Shade with wooden primer as per existing colour.	85.19	M2
3	Provision for painting two or more coat of synthetic enamel paint to the old wooden work of temple including preparing base etc.	496.22	M2
4	Provision for Supply and Fixing of Mangalore Tiles/ Terracotta Tiles and Resetting the same on the roof of the Shabha Garah (Front Portion)of the Temple (40% old and 60% New).	563.52	M2
5	Provision for Resetting of Old Ancient Stone Flooring of Bhairamdev Sculpture Present in the Shabha garah of Main danteshwari Temple.	4.48	M2
6	25 mm thick KOTA stone slab flooring over 20mm (Average) thick base of cement mortar 1:4 laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including grinding rubbing and polishing etc. complete.	355.26	M2
7	Providing and fixing stainless steel railing made of Hollow tubes, channels, plates, chain etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size as per approval of Engineer-in-charge.	627.9	KG
8	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge.	56.4	M3
9	Provision for Coursed rubble Stone masonry with in lime mortar 1:1:1(one lime-Unslaked, one corse Sand, one Surkhi First Class) including supply of material, labour, T&P etc Complete (Boundary Wall using 60 % new Stone and 40 % Old Sand).	56.4	M3
10	Providing and laying of 40 to 50mm thick Cist stone plate Flooring using 100% New Stone over 20mm(Average) thick Base of lime mortar in ratio 1:1:1 with joints 3 mm thick , side buttered with same mortar admixture with pigment to match the shade of structure and pointing same mortar including chiseling of the stone properly.	1012.96	M2
11	Provision for Repair of damaged wall of Bhairamdev temple- Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge	3.8	M3
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand).	3.8	M3



