

23/12/19

File No. RPR/03/19-20/QC-160
Government of India
Office of the Conservation Assistant
Archaeological Survey of India
Raipur Sub-Circle, Raipur

"Poorvayatan" 1st Floor,
Govind Sarang Commercial Complex,
New Rajendra Nagar, Raipur, C.G.
Dated 23/12/19

QUOTATION CALL NOTICE

Sealed quotations are hereby invited from the intended contractors/firms having valid registration for the execution of following items for the work OW to Maintenance of toilet block at Laxman Temple, Sirpur up to 06.01.2020.

The Sealed quotation must be addressed to "The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan" 1st Floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur, C.G.-492006 & will be received in the O/o The Conservation Assistant, ASI, Raipur Sub-Circle, "Poorvayatan" 1st Floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur, C.G.-492006 up to 3.00P.M. of 06.01.2020

- The quotation will be opened on 06.01.20 at 3.30 P.M. in the above said office.
- The competent authority reserved the right to accept or reject any or all quotation without assigning any reason thereof.

| Item No | Particulars | Quantity | Rate | unit | Amount |
|---------|--|----------|------|------|--------|
| 01 | Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of Serviceable material within 50 meters lead as directed by Engineer-in-charge. | 12.17 | | Sqm | |
| 02 | Providing and Fixing factory made uPVC door Including fixing the frame with jamb with required number & size of anchor dash fasteners, all complete as per manufacturer's specification and direction of Engineer-in-charge. | 5.0 | | Each | |
| 03 | Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern | 2.0 | | Each | |

आगत क्र. सं./Inward Dy. No. 2224
दिनांक/Date: 23/12/19
भारतीय पुरातत्व सर्वेक्षण
Archaeological Survey of India
राजपुर मण्डल, राजपुर (छ.ग.)
Raipur Circle, Raipur (C.G.)

| | | | | | |
|-------|---|-------|--|------|--|
| 04 | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm | 27.89 | | Sqm | |
| 05 | Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete. | 27.89 | | Sqm | |
| 06 | Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying as per description given in DSR 2018 Item No 22.6 | 74.52 | | Sqm | |
| 07 | Provision for supply and fixing of minor repairing of water supply and sanitary fittings etc complete | | | | |
| i. | CPVC Pro 25mm Coupling | 12 | | Each | |
| ii. | CPVC Pro Tank Adaptor | 4 | | Each | |
| iii. | Metro 1-1/2 Inch Brass Ball Valve [EACH] | 2 | | Each | |
| iv. | CPVC Pro CTS Ball Valve [EACH] | 4 | | Each | |
| v. | CPVC Pro 90 Deg Elbow [EACH] | 13 | | Each | |
| vi. | CPVC Pro 90 Deg Brass Elbow[EACH] | 8 | | Each | |
| vii. | CPVC Pro Brass FPT Tee [EACH] | 14 | | Each | |
| viii. | Stainless Steel Heavy Duty Connection Pipe [EACH] | 6 | | Each | |
| ix. | Plastic Double Layered Water Tank, 1000 L [EACH] | 1 | | Each | |
| x. | 1" pvc pipe [RMT] | 24 | | RMT | |
| xi. | 1.5" pvc pipe [RMT] | 16 | | RMT | |
| xii. | Newway Brass Round Angle Cock[EACH] | 7 | | Each | |
| xiii. | ABS Health Faucet With SS-304 Grade 1.25 Meter Flexible Hose Pipe and Wall Hook [EACH] | 3 | | Each | |
| xiv. | Quarter Turn Cock C.P Fittings Tap with water Saving Aerator [EACH] | 8 | | Each | |
| xv. | wash basin [EACH] | 3 | | Each | |
| xvi. | Contractor Profit 10 % [EACH] | 1 | | Each | |
| | ∴ Total of item | | | | |
| 08 | Provision for supply and fixing of electrical items as per requirement of work complete | | | | |
| i. | LED 20 W | 6 | | Each | |
| ii. | Bulb Holder | 5 | | Each | |
| iii. | Havells 2.5 Sq mm Single Core (90m bundle) | 2 | | Each | |
| iv. | 3M White Chrome Modular Plate | 4 | | Each | |
| v. | Modular Switch | 12 | | Each | |
| vi. | Modular Sockets | 6 | | Each | |
| vii. | Tube Lights | 3 | | Each | |
| viii. | Switch Board Box | 3 | | Each | |

| | | | | | |
|-------------|--|---|--|------|--|
| ix. | Contractor Profit 10 % | 1 | | Each | |
| | Total of item | | | | |
| 10 | GST 12 % (Except Item no 01, 03, 04, 05, 06) | | | | |
| Grand Total | | | | | |

(Ashis Vashisth)
Raipur Sub-Circle(I/c)

Copy to –

1. Sh. S.K. Baghel, Baniyapara, Ratanpur
2. Sh. Prahlad Kashyap, Bhedimuda, Ratanpur
3. Sh. Ram Kishore Jha, Shriram Nagar, Raipur
4. Sh. Dhananjay Jha, Bilaspur
5. M/s Maa Sharda Construction, Bilaspur
6. Sh. Sudhir Jha, Ganganagar ward, Jagdalpur
7. S.A.A.S.I. Raipur Circle, for kind information with the request to kindly upload on website
8. Notice Board

Ashis Vashisth
23/12/19
(Ashis Vashisth)
Raipur Sub-Circle(I/c)