

15/01/20  
2020

File No. JOP/01/19-20/OC-38

Government of India

Office of the Conservation Assistant

Archaeological Survey of India

Jagdalpur Sub-Circle, Jagdalpur

Dated 15-01-2020

**QUOTATION CALL NOTICE**

Sealed quotations are hereby invited from the intended contractors/firms having valid registration for the execution of following items for the work OW to of store shed & staff quarter, toilet block at Danteshwari temple, Dantewada up to 22.01.2020.

The Sealed quotation must be addressed to "**The Superintending Archaeologist, Archaeological Survey of India, Raipur Circle, "Poorvayatan" 1st Floor, Govind Sarang Commercial Complex, New Rajendra Nagar, Raipur, C.G.-492006** & will be received in the **O/o The Conservation Assistant, ASI, Jagdalpur Sub-Circle, , HIG DD-II, Housing Board Colony, Aghanpur Kangoli, Dharampura Phase-I, Jagdalpur, District-Bastar Jagdalpur, Chhattisgarh C.G.-492006** up to 3.00P.M. of 22.01.2020

- The quotation will be opened on 23.01.2010 at 3.30 P.M. in the O/o SAASI Raipur Circle, Raipur.
- The competent authority reserved the right to accept or reject any or all quotation without assigning any reason thereof.

S.No	Name of item	Quantity	Rate	Per unit	Amount
1	"Dismantling tile (toilet block in front of staff quarter) work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	19.4		M2	
2	"Providing and laying Ceramic glazed floor tiles (toilet block in front of staff quarter) of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	19.4		M2	
3	"Providing and laying water proofing treatment (toilet block in front of staff quarter) on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying as per instruction given by Engg. incharge	62.3		M2	

आवक सं. / Inward Dy. No. 2430

दिनांक / Date: 15/01/20

भारतीय पुरातत्व सर्वेक्षण

Archaeological Survey of India

जगदलपुर उपखण्ड, रायपुर (छ.ग.)

Raipur Circle, Raipur (C.G.)

4	"Provision for Distempering with oil bound washable distemper ( Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple ) of approved brand and manufacture to give an even shade Old work (one or more coats) "	52.02		M2	
5	"Provision for Finishing outer walls with textured exterior paint (Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple)of required shade (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	115.62		M2	
6	" Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge ( toilet block infort of staff quater ) & ( Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple )	7.34		M2	
7	" Providing and Fixing factory made uPVC door Including fixing the frame with jamb with required number & size of anchor dash fastners, all complete as per manufacturer's specification and direction of Engineer-in-charge. [EACH] ( toilet block infort of staff quater ) & ( Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple )	4.0		EACH	
8	Provision for supply and fixing of minor repairing of water supply ,sanitary fittings & electrical items etc complete (Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple)				
8(A)	Plastic water tank (1000 lt ) , toilet block infort of staff quater & staff quarter ( plasto /sintex company) with transport & install.	2.0		EACH	
8(B)	0.5INCH Water Pipe Stainless steel with install & transport charge as RMT or LOCAL RATE	25.0		[RMT]	
8(C)	Contractor Profit 10 %	1.00		[EACH]	
8(D)	LED 20 W	6.00		[EACH]	
8(E)	Havells 2.5 Sq mm Single Core (90m bundle)	2.00		[EACH]	
Sub Total					
9	"Provision for purchase of items for better upkeepment of toilet block , staff quater & store shade				

9(A)	Ceiling fan ( Havells, Polar of Usha) for staff quater	1.00		[EACH]	
9(B)	Exhaust Fan ( usha , havells )	2.0		[EACH]	
Sub Total					
10	Providing and laying in position cement concrete of specified grade 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering for damage P.C.C. infornt of Toilet block for Man, Women & Phy. Hand. back side of bhuvneswari devi temple) up to 40 mm thick .	2.89		M3	
11	GST 12 % (On Item no,07,08,09)				
Grand TOTAL					

(Sreyash Sharma)  
Jr. Conservation Assistant  
Jagdalpur Sub-Circle

Copy to -

1. Sh. S.K. Baghel, Baniyapara, Ratanpur
2. Sh. Prahlad Kashyap, Bhedimuda, Ratanpur
3. Sh. Ram Kishore Jha, Shriram Nagar, Raipur
4. Sh. Dhananjay Jha, Bilaspur
5. M/s Maa Sharda Construction, Bilaspur
6. Sh. Sudhir Jha, Ganganagar ward, Jagdalpur
- ✓ 7. S.A.A.S.I. Raipur Circle, for kind information with the request to kindly upload on website
8. Notice Board

*Sreyash Sharma*  
15-01-2020  
(Sreyash Sharma)  
Jr. Conservation Assistant  
Jagdalpur Sub-Circle